

TABLE XXXVIII.
LABOR IN ERECTION.

Span.	12' Roadway.	14' Roadway.	16' Roadway.	18' Roadway.	20' Roadway.	22' Roadway.	24' Roadway.
40'	17	18	19	20	21	22	23
50'	19	21	23	25	27	29	31
60'	24	26	28	30	32	34	36
70'	39	41	43	45	47	49	51
80'	46	49	52	55	58	61	64
90'	56	59	62	65	68	71	74
100'	63	67	71	75	79	83	87
110'	75	80	85	90	95	100	105
120'	87	93	99	105	111	117	123
130'	104	111	118	125	132	139	146
140'	126	134	142	150	158	166	174
150'		160	170	180	190	200	210
160'		191	203	215	227	239	251
170'		222	236	250	264	278	292
180'		253	269	285	301	317	333
190'		284	302	320	338	356	374
200'			335	355	375	395	415
210'			373	395	417	439	461
220'			416	440	464	488	512
230'			463	490	517	544	571
240'			510	540	570	600	630
250'			557	590	623	656	689
260'			614	650	686	722	758
270'				710	749	788	827
280'				770	813	856	899
290'				830	876	922	968
300'				890	940	990	1040